


TYPE 'A' = AMERICAN ELM ULMUS AMERICANA **Schedule**

Landscape / Hardscape

- NEW WOOD FENCING NEW CONCRETE WALK - MIN 5'-0" WIDTH / MAX SLOPE 1:14 BROOM FINISH / EXPANSION JOINTS MIN 7'-0" O.C.
- NEW CONCRETE SLAB BROOM FINISH / EXPAN 16'-0" O.C. BOTH DIRECTIONS

5 4 3 2

EXISTING TREES TO REMAIN





OPSOIL SHALL BE FREE OF SUBSOIL, WOOD, INCLUDING WOODY PLANT ARTS, WEEDS & REPRODUCTIVE PARTS OF WEEDS, TOXIC MATERIALS, TONES OR DEBRIS OVER ONE HALF (1/2) INCH IN SIZE. TOPSOIL SHALL OT BE MIXED WITH SUBSOILS, MOVED, OR WORKED WHILE IN A WET OR ROZEN CONDITION.

BWI Development & Management, Inc. 5902 East 34th Street Indianapolis, Indiana 46218 317.468.9902 www.bwillc.com



THE SITE IS TO BE LEFT IN A CLEAN AND NEAT CONDITION AT ALL TIMES

REMOVE ALL PLASTIC AND WIRE TAGS AND CORDS FROM PLANT MATERIALS PRIOR TO NSTALLATION.

CARIFY SIDES AND BOTTOM OF PLANTING PIT. FOLD BACK THE TOP HIRD OF BURLAP ON ROOT BALL.

HE ARCHITECT SHALL INSPECT THE QUALITY OF PLANT MATERIAL UPON ARRIVAL ON-SITE EFORE PLANTS ARE PLACED IN THE GROUND. THE ARCHITECT MAY REJECT ANY PLANT ATERIAL, AND IT SHALL BE REPLACED WITH ACCEPTABLE MATERIAL BY THE LANDSCAPE UB-CONTRACTOR.

General Notes

THE LANDSCAPE SUB-CONTRACTOR SHALL PROVIDE THE OWNER SEPARATE QUOTATION FOR A DIVE-YEAR MAINTENANCE CONTRACT INCLUDING WATERING, WEEDING, AND INSECT AND DISEASE CONTROL.

Landscape

1030 North Central Suite I Indianapolis, Indiana 46202 317.345.5094 brent@robertandbrent.com